

City of Takoma Park

LED Retrofit Projects

Presented by:

Gina Mathias, Sustainability Manager Nima Upadhyay, Special Projects Coordinator

MD Smart Energy Community

- Goal: Reduce per square foot electricity consumption by 15% by FY 2017 over baseline FY 2012
- Develop Projects to achieve the goal
- Grant from MEA to complete projects

<u>Baseline</u> Year Energy Consumption - FY 2012											
Building Type and Address	Status	Building Size	Electricity Conventional	Electricity Renewable	Electricity Total	Electricity Consumption Intensity					
	Ownership	Gross Square Feet	ross Square Feet kWh kWł		kWh	Total kWh/SF					
Community Center	City Owned	62,000	436,320	25,250	461,570	7.4447					
Public Works	City Owned	21,464	128,400	0	128,400	5.9821					
Heffner Park Community Center	City Owned	1,488	13,680	0	13,680	9.1935					
**New Hampshire Rec Center Leased/Owned by M-NCPPC		2,964	120,760	0	120,760	40.7422					
Total		87,916	699,160	25,250	724,410	8.2398					

SMEC- Project -Building

- Buildings: Completed in every feasible municipal building
 - Recreation Center (LED Retrofit)
 - Baseline: Metal Halide 200W, magnetic ballast gym light
 - Hefner Park Recreation Building (HVAC Improvements)
 - Community Center (LED Retrofit)
 - Baseline: Fluorescent, (2) 48", T-8 lamp
 - o (Public Works LEED Silver Certified in 2011, low priority, but planned)



LED Streetlight Pilot for Flower Ave Green Street

- Transportation study showed lighting was inadequate for the entire Flower Avenue Corridor.
- Pepco LED retrofit option available.
- CDBG funds provided for project.

- 49 streetlights converted to LED.
- Mostly 70 100 Watt
- Energy savings estimated:
- 1 for 1 replacements however lumens increased
- Western side LED
- Eastern side will include new decorative lamps.



Project Costs*

- Building LED Projects:
- Recreation Center
 - Total Cost =50,169
 - o **\$29,191**
 - Pepco Rebate: 20,978
- Community Center
 - Total Cost =\$34,842
 - 。\$13,864
 - Pepco Rebate: 20,978
- Hefner HVAC Project
 - 。 \$8,695
 - Pepco Rebate: None

- Streetlight Pilot Project:
 - 0 \$77,549.00
 - o Rebate TBD

*All project costs covered by MEA or CDBG grants



Streetlight Energy Savings

Existing Fixture	Wattage	Number	Proposed Fixture	Wattage	Number
High Pressure Sodium	100	9	LED-ACUITY AEL	100	9
High Pressure Sodium	150	6	LED-ACUITY AEL	70	5
High Pressure Sodium	100	28	LED-ACUITY AEL	70	28
High Pressure Sodium	250	6	LED-ACUITY AEL	70	6
High Pressure Sodium	250	1	LED-ACUITY AEL	100	1

Project annual KWh saving = 20,012 KWh

Lessons Learned / Reactions

• Buildings:

- Initial retrofits had to be adjusted "too bright"
- Lesson must complete a proper lighting study to look at
 - Color temperature, lumens, directional spray
- Positive feedback on the updated, modern fixtures
- Dimming capability is a positive
- No humming/buzzing is a positive
- Cost savings positive
- Brighter, more inviting, easier to see
- Funding projects is difficult, rely on grants not CIP budget typically
- Creating attractive grant proposals without very large gains difficult, especially after achieving initial 15% reduction in energy use.

Lessons Learned / Reactions

• Streetlights:

- Residents have not noticed or at least have not commented
- Staff is pleased with aesthetic and performance SO FAR
- Financial savings positive
- Encouraged to complete more comprehensive street lighting retrofits
- Eventually, "smart" controls will be available for dimming, reporting, real-time monitoring
- Rebate process was not as easy or transparent
- Still a new process for Pepco and municipalities