## Stream Restoration Crediting for Meeting Sediment and Nutrient Goals in the Chesapeake Bay





COG Stream Restoration Technical Session

> Bill Stack Lisa Fraley-McNeal

February 25, 2014



Chesapeake Bay Program A Watershed Partnership

## Sediment Reduction and Stream Corridor Restoration Analysis, Evaluation and Implementation Support to the Chesapeake Bay Program Partnership

#### I. Provide Modeling Support

Estimate upland and in-stream sediment contributions through a scientific literature review and data analysis.

#### II. Coordinate Partnership Scientific Input

- Urban Stream Restoration Expert Panel
- Shoreline Erosion Control Expert Panel
- Urban Filter Strip/Stream Buffer Upgrade Expert Panel

#### III. Programmatic Evaluation, Reporting and Verification

- Stream restoration verification principles
- STAC workshop Designing Sustainable Stream Restoration Projects within the Chesapeake Bay Watershed
- Stream health workgroup

## **Expert Panel on Stream Restoration**

Expert BMP Review Panel for Urban Stream Restoration			
Panelist	Affiliation		
Deb Cappuccitti	Maryland Department of Environment		
Bob Kerr	Kerr Environmental Services (VA)		
Matthew Meyers, PE	Fairfax County (VA) Department of Public Works and		
	Environmental Services		
Daniel E. Medina,Ph.D, PE	Atkins (MD)		
Joe Berg	Biohabitats (MD)		
Lisa Fraley-McNeal	Center for Watershed Protection (MD)		
Steve Stewart	Baltimore County Dept of Environmental Protection and		
	Sustainability (MD)		
Dave Goerman	Pennsylvania Department of Environmental Protection		
Natalie Hardman	West Virginia Department of Environmental Protection		
Josh Burch	District Department of Environment		
Dr. Robert C. Walter	Franklin and Marshall College		
Dr. Sujay Kaushal	University of Maryland		
Dr. Solange Filoso	University of Maryland		
Julie Winters	US Environmental Protection Agency CBPO		
Bettina Sullivan	Virginia Department of Environmental Quality		
Panel Support			
Tom Schueler	Chesapeake Stormwater Network (facilitator)		
Bill Stack	Center for Watershed Protection (co-facilitator)		
Other Panel Support: Russ Dudley - Tetra Tech, Debra Hopkins - Fish and Wildlife			
Service, Molly Harrington, CBP CRC, Norm Goulet, Chair Urban Stormwater Work			
Group, Gary Shenk, EPA CBPO, Jeff Sweeney, EPA CBPO, Paul Mayer, EPA ORD			

## The Panel Process

- Outlined in the BMP Review Protocol (WQGIT, 2010)
- BMP Expert Panel → reviews existing research → set of recommendations
- 7 calls, 2 workshops, 5 drafts over 12 months
- Product: Technical Memo and 5 Appendices



The Agriculture Work Group, Watershed Technical Workgroup and Stream Habitat GIT is also actively involved in the review process.



## How Sediment and Nutrients are Simulated in the CBWM

Sediment Delivery The Project Reach versus the CBWM River Basin Segment



### **Review of the Old Rate**

Initial CBP-Approved Stream Restoration Credit (2003)

Removal Rate per Linear Foot of Qualifying Stream Restoration				
Source	TN	TP	TSS	
Spring Branch N=1	0.02 lbs	0.0035	2.55 lbs	
At some point applied to non-urban stream restoration projects.				

#### Approved Interim Rate

Edge-of-Stream 2011 Interim Approved Removal Rates per Linear Foot of Qualifying Stream Restoration (lb/ft/yr)					
Source	TN	ТР	TSS*		
New Interim CBP Rate	0.20	0.068	310 (54.2)		
Derived from six stream restoration monitoring studies: Spring Branch, Stony Run, Powder Mill Run, Moore's Run, Beaver Run, and Beaver Dam Creek located in Maryland and Pennsylvania *The removal rate for TSS is representative of edge-of-field rates and is subject to a sediment delivery ratio in the CBWM to determine the edge-of-stream removal rate. Additional information about the sediment delivery ratio is provided in Appendix B.					

## Why the initial credit needed to be changed and a universal restoration credit doesn't make sense



## Protocol 1: Credit for Prevented Sediment during Storm Flow

This protocol provides an annual mass nutrient and sediment reduction credit for qualifying stream restoration practices that prevent channel or bank erosion that would otherwise be delivered downstream from an actively enlarging or incising urban stream.

- Estimate stream sediment erosion rates
- Convert erosion rates to nitrogen and phosphorus loadings
- Estimate reduction efficiency attributed to restoration

# Recommended Methods

- Monitoring
  - Surveyed cross sections, bank pins...
- BANCS method
  - With validation
- Alternative modeling approach
  - Or other methods with validation (e.g., CONCEPTS, BSTEM, stepwise regression)

## Protocol 1: Credit for Prevented Sediment during Storm Flow

### Step1. Estimate Stream Sediment Erosion Rates Using the BANCS Method



Streambank Characteristics used to develop BEHI

Velocity			
Gradient and			
Near-Bank			
<b>Stress Indices</b>			

Bank Erosion Risk Rating	Velocity gradient	Near-bank stress/shear stress
Very low	Less than 0.5	Less than 0.8
Low	0.5 -1.0	0.8 -1.05
Moderate	1.1 -1.6	1.06 -1.14
High	1.61 - 2.0	1.15 - 1.19
Very High	2.1 -2.4	1.20 -1.60
Extreme	Greater than 2.4	Greater than 1.60

## Protocol 1: Credit for Prevented Sediment during Storm Flow

Regional Curve for Determining "R" in equation:  $S = \sum (C \times A \times R)$ 



### Protocol 2: Credit for Denitrification in the Hyporheic Zone during Base Flow

Step 1. Determine the total post construction stream length that has been reconnected using the bank height ratio of 1.0 or less (for NCD) or the 1.0 inch storm (other design approaches that do not use the bank full storm)

Step 2. Determine the dimensions of the hyporheic box

Step 3. Multiply the hyporheic box mass by the unit denitrification rate



### **Protocol 3: Credit for Floodplain Reconnection**





# Basis for Protocol 3 Curves

Relationship between nutrient removal and ratio of wetland area to watershed area



Study by Jordan, Smithsonian Environmental Research Center, as published in Weammert and Simpson, 2009. The proportion of TN and TP removed increases with the proportion of wetland area, but the rate of increase declines as the proportion of wetland area increases. Thus, the additional benefit of adding more wetland area gradually diminishes.

### Protocol 3: Credit for Floodplain Reconnection Volumes

Step 1. Estimate the floodplain connection volume

Step 2. Estimate the N and P removal rate attributable to floodplain reconnection (using Jordan 2007 study)



## **Qualifying Conditions**

- Stream restoration projects that are primarily designed to protect public infrastructure by bank armoring or rip rap do not qualify for a credit.
- The urban stream reach must be greater than 100 feet in length
- The project must utilize a comprehensive approach to stream restoration design, involving the channel and banks.
- Stream restoration project must provide a net watershed removal benefit in order to be eligible for either a sediment or nutrient credit.
- No removal credit will be granted for any project that is built to offset, compensate, or otherwise mitigate for an impact to a stream or waterway elsewhere in the watershed

## **Environmental Concerns**

- Each project must comply with all state and federal permitting requirements.
- Stream restoration should not be implemented for the sole purpose of nutrient or sediment reduction.
- A qualifying project must meet certain presumptive criteria to ensure that highfunctioning portions of the urban stream corridor are not used for in-stream stormwater treatment (i.e., where existing stream quality is still good).
- Stream restoration should be directed to areas of more severe stream impairment, and the use and design of a proposed project should also consider the level of degradation, the restoration needs of the stream, and the potential functional uplift.
- Before credits are granted, stream restoration projects will need to meet postconstruction monitoring requirements, document successful vegetative establishment, and conduct initial project maintenance.
- A qualifying project must demonstrate that it will maintain or expand riparian vegetation in the stream corridor, and compensate for any project-related tree losses in project work areas.
- All qualifying projects must have a designated authority responsible for development of a project maintenance program that includes routine and long-term maintenance.

## **Initial Verification of Performance**

 Prior to submitting the load reduction to the state tracking database, the installing agency will need to provide a post-construction certification that the stream restoration project:

Owas installed properly,

Omeets or exceeds its functional restoration objectives Ohydraulically and vegetatively stable,

• Initial verification is provided either by the designer, local inspector or state permit authority

## Verification of Stream Restoration Credit

- Max duration for the removal credits is 5 years
- Credit is renewed based on a field performance inspection that verifies the project still exists, is adequately maintained and operating as designed.
- Credit is lost if project cannot be verified (i.e., does not pass inspection).
- This creates strong incentive for localities to monitor the long term performance of their projects

## The "Test-Drive" Process

- Recommended protocols are new, somewhat complex and will require project-based interpretation on the part of practitioners and regulators alike.
- Five consulting firms and one local government applied the protocols to ten different projects over the 6-month test drive period.

## Main Concerns I dentified during the "Test-Drive" Process

#### General Concerns

- The protocols are too complicated and difficult to use for planning purposes.
- The interim rate leads to load reductions that can exceed watershed loading rates and may preclude the use of more robust protocols.
- Protocol 1 Concerns
  - The BANCS method may not be accurate and regional curves have not been developed.
  - The 50% efficiency requirement is too low.
  - Confusion over application of the sediment delivery factor.
- Protocol 2 Concerns
  - Certain types of projects result in load reductions that can exceed watershed loading especially for Protocol 2.
- Protocol 3 Concerns
  - The curves used to develop Protocol 3 are not accurate enough for design purposes.
  - The pre-restoration condition was not accounted for.
  - Confusion over how upstream BMPs will affect load to the project and subsequently the credit received.
  - Confusion over why the baseflow TN credit from Protocol 2 is not added to the credit from Protocol 3.

## **General Protocol Revisions**

Concern: The protocols are too complicated and difficult to use for planning purposes.

Solution: Made it clear in the report that the interim rate is used for planning purposes and projects that do not conform to recommended reporting requirements.

## **General Protocol Revisions**

Concern: The interim rate leads to load reductions that can exceed watershed loading rates. The interim rate may also preclude the use of more robust protocols.

Solution: The interim rate was adjusted to account for application of reduction efficiencies to TN and TSS.

Justification: An analysis of the Baltimore City data upon which the interim rate was based, revealed that a 50% efficiency was applied to TP, but not for TN and TSS.

## **Protocol 1 Revisions**

Concern: The BANCS method may not be accurate and regional curves have not been developed.

- Solution: Clarified that states are encouraged to develop their own more robust methods for estimating streambank erosion rates.
- Concern: Confusion over application of the sediment delivery factor (SDF).
- Solution: Added in a better description of the SDF, how the average SDF can be applied for planning purposes, and that the loads should be reported without the SDF applied because that is done in Scenario Builder.

## **Protocol 1 Revisions**

Concern: The 50% restoration efficiency may be too low and is based on only one study.

Solution: Allowed greater than 50% restoration efficiency for projects that include monitoring to demonstrate higher rates such as Big Spring Run.

Justification: A greater incentive for monitoring will be created to achieve higher restoration efficiencies. This change will benefit projects, such as Big Spring Run, which showed greater than 70% sediment reduction.

## Protocol 2 Revisions

Concern: Load reductions from Protocol 2 can be high and in some cases exceed watershed loading rates.

Solutions:

- Added a qualifying condition that TN load reduced cannot exceed 40% of the total watershed TN load.
- Original denitrification rate (1.95  $\times$  10<sup>-4</sup> lbs N/ton/day of soil) was an average of the low bank restoration sites in Minebank Run. Revised the rate so it is an average of both the high and low bank restoration sites (0.96  $\times$  10<sup>-4</sup> lbs N/ton/day of soil).

Justification: Klocker (2009) found that 40% of the daily load of nitrate in Minebank Run could be removed. In addition, the lower denitrification rate would provide a more conservative estimate to account for the variability in measured denitrification rates.

## **Protocol 3 Revisions**

Concern: The curves used to develop Protocol 3 are not accurate enough for design purposes.

Solution: Included a better description of how the curves were developed and how other methods can be used, such as an alternate method presented in Appendix G that uses the Soil Conservation Service Runoff Curve Number.

Concern: The pre-restoration condition was not accounted for in the Protocol.

Solution: Included pre-restoration assessment and qualifying conditions.

## **Protocol 3 Revisions**

Concern: Confusion over how upstream BMPs affect load to the project and subsequently the credit received.

Solution: The CBP Modeling Team will provide further explanation in Appendix F, which addresses modeling concerns related to Scenario Builder.

## **Protocol 3 Revisions**

Concern: Confusion over why the baseflow TN credit from Protocol 2 is not added to the credit from Protocol 3.

Solution: Added an explanation of why Protocol 3 accounts for baseflow and stormflow (i.e., pervious and impervious loading to the project). Protocols 2 and 3 are also be allowed to be additive.

Justification: After a review of Protocol 3, it was found that the baseflow load reduction was not adequately represented.

## Next Steps

- Appendix F to be completed this winter that addresses modeling concerns.
- User Training?

## Questions?