

# Nash Run Stream Restoration Project

MWCOG Stream Restoration Technical Session



Aquatic Gardens

Kenilworth

Project Site

Deanwood

Nash Run Watershed

Eastland Gardens

Burrville

Prince Georges County  
District of Columbia



# Nash Run





# Present Site Conditions

- Watershed size: 0.7 sq miles
- Stream Length: 1430ft
- Private Properties: 50+
- Load to the Anacostia: 33.5 tons/yr. erosion





FEMA 100yr. Floodplain







Trash



Poor In-Stream Habitat



Bank Erosion





# Upstream Trash Trap






# Floodplain Reconnection Design

- Create a low floodplain bench in relation to current stream elevation
- Remove 9500 cubic yards of stream bank
- Create 6” floodplain on both sides of stream
- Highly connected riparian zone











# Protocols Used

- Protocol 1: Prevented Sediment
  - 345ft monitored segment over 15 months with bank pins and soil testing
- Protocol 2: In-Stream Nutrient Processing
  - Estimated hyporeic zone calculation
- Protocol 3: Floodplain Reconnection
  - Too small of an area for watershed size (0.22% floodplain area to watershed size)
- ~~Protocol 4: Dry Channel RSC~~



# Protocol 1

- **Project Length:** 1269.2 linear feet.
- **Monitored Length:** 345 linear feet, or 27 percent Nash Run.
- **Calculation:** The computed total annual stream bank erosion rates extrapolated from the existing stream bank monitoring data is as follows:  
$$(33.5 \text{ tons/yr}) / (345 \text{ ft}) = 0.0971 \text{ tons/yr/ft}$$
$$1269.2 \text{ ft} * 0.0971 \text{ tons/yr/ft} = 123.2 \text{ tons/yr}$$
- **Reductions- Nitrogen: 295.8 lbs/yr.; Phosphorus: 94.9 lbs/yr.; and TSS: 123.2 tons/yr.** based on an avg. soil density value of 2600 lbs / cubic yard (conversion factor of 1.3 for yd<sup>3</sup> to tons for avg. materials).



# Protocol 2

- **Project Length:** 1269.2 feet
- **Channel Width:** 10 feet
- **Calculations:**
  1.  $[(5 \text{ ft}) + (10 \text{ ft}) + (5 \text{ ft})] * 5 \text{ ft} * 1269.2 \text{ ft} = 126,920 \text{ ft}^3$  (vol. hyporheic box)
  2.  $126,920 \text{ ft}^3 * / 27 \text{ ft}^3 / \text{cy} = 4700.7 \text{ cy}$
  3.  $(4700.7 \text{ cy} * 2600 \text{ lbs/cy}) / 2000 \text{ lbs/ton} = 6,111 \text{ tons}$
  4.  $0.000195 \text{ lbsN/ton/day} * 6111 \text{ tons} * 365 \text{ day/yr} = \underline{434.9 \text{ lbs nitrogen/yr}}$



# Protocol 3

- **Watershed Area:** 467.2 acres
- **Estimated Floodplain Area:** 1.05 acres
- **Floodplain/Watershed:** .22% (not the 1% threshold needed)
- *Credit is miniscule due to small floodplain to watershed area ratio.*
- *Floodplain reconnection design but not much floodplain reconnection credit ☹️*



# Load Reduction Comparison

Method	TN	TP	TSS
Old Rate	50.8 lbs/yr	8.8 lbs/yr	6472.9 lbs/yr
Interim Rate	190.4 lbs/yr	172.6 lbs/yr	110,166.6 lbs/yr
Protocol 1	295.8 lbs/yr	94.9 lbs/yr	246,482 lbs/yr
Protocol 2	434.9 lbs/yr		
Protocol 3	0.08 lbs/yr	0.01 lbs/yr	4.90 lbs/yr
<b>Protocol 1+2+3</b>	<b>730.8 lbs/yr</b>	<b>94.9 lbs/yr</b>	<b>246,487 lbs/yr</b>





# Legacy Sediment Projects

- At Nash Run 9,500 cubic yards is being removed to create a low floodplain bench. Our design team, JMT, estimates that could be a one time removal credit of:
  - 29,640 lbs of N
  - 9,510 lbs of P
- Would this give perverse incentive to excavate unnecessarily or is it the right thing to do?



# Lessons Learned

- Accuracy vs. Simplicity and Associated Costs
- Include calculations in design scopes of work
- Training needed
- Must do it to learn it



# Big Thanks!!!



DISTRICT  
DEPARTMENT  
OF THE  
ENVIRONMENT

