

PHASE I POST CONSTRUCTION MONITORING FOR DC CLEAN RIVERS PROJECT

**Briefing for:
Water Resources Technical Committee Meeting**

September 8, 2017

Carlton M. Ray

(Director, DC Clean Rivers Project, DC Water)

John Cassidy

Program Manager, DC Clean Rivers, Greeley and Hansen

Agenda

- DC Clean Rivers Background
- Phase I Post Construction Monitoring
- Summary of *E.coli* Results
- Conclusions
- Questions



DC Clean Rivers Background Magnitude of the Challenge

► Combined Sewer Overflows



CSO Discharge to Anacostia River



Trash in Anacostia River

On average, **2.1 billion gallons** of untreated sewage and stormwater runoff (combined sewage) are discharged to the Anacostia River per year.

► Chronic Sewer Flooding



▲ Flooding on Mt. Olivet Rd NE



▲ Flooding on Rhode Island Ave NE



▲ Flooding on Rhode Island Ave NW




▲ Flooding on Flagler Pl NW



▲ Flooding at 1st and V Streets NW



▲ Flooding at 1st and Rhode Island Ave NW




▲ Flooding at Shaw metro





▲ Flooding at 1st and P Streets NW

Chance of flood occurring in any given year




DC Clean Rivers Project



DC CLEAN RIVERS PROJECT AND NITROGEN REMOVAL PROGRAMS

- DC Clean Rivers Project: \$2.6 Billion
- Nitrogen Removal: \$950 Million
- Total > \$ 3.5 Billion
- 25 yr implementation (2005 – 2030)
- 96% reduction in CSOs & flood relief in Northeast Boundary
- Approx 1 million lbs/yr nitrogen reduction predicted


Anacostia River Tunnel System Snapshot



Project	Diameter	Length	Start	Finish
Blue Plains Tunnel (\$318M)	23	24,207	5/2011	8/2015
First Street Tunnel (\$158M)	20	2,700	10/2013	10/2016
Anacostia River Tunnel (\$254M)	23	12,484	6/2013	12/2017
Northeast Boundary Tunnel (\$580M)	23	27,000	9/2017	2023

Various other contracts to connect to tunnel system

More than \$1.8 B in Contracts have been let for the Anacostia River Projects



PHASE I POST CONSTRUCTION MONITORING - SUMMARY

Overview

- NPDES Permit Requirements:

Phase	Post-construction Condition
1	Following placement in operation of the inflatable dams and pumping stations rehabilitation
2	Following placement in operation of the Anacostia, Rock Creek and Potomac Storage tunnels, respectively as each tunnel is placed in operation
3	Following placement in operation of the complete CSO Tunnels storage system

- Phase I Monitoring - Duration


- Data Collection Period: 12/1/2014 – 2/16/2016
- Report sent to EPA on August 12, 2016

- Phase I Monitoring – Scope

Component	Who Performed
Rainfall Monitoring	CSL & OneRain
CSO Overflow & In-system Monitoring	CSL
CSO Overflow Sampling	DC Clean Rivers
Receiving Water monitoring	
Continuous Dissolved Oxygen	MWCOG /Versar
Regular sampling	MWCOG /Versar
Wet Weather Surveys	MWCOG /Versar

Rainfall, Flow & CSO Sampling – Locations


- Additional Rainfall Data Used:
 - National Weather Service Gage at Ronal Reagan Nat'l Airport
 - Radar data (1km x 1km grid)



Receiving Water Monitoring Summary





Receiving Water	# of Stations	No. of Sampling Events	Parameters Collected
Anacostia	5	71- Regular Sampling 4- Wet Weather Surveys	Fecal Coliform, E. Coli, CBOD5, TSS, Chlorophyll-a Field Parameters- Ph, D.O., Temperature, Conductivity
Potomac	4		
Rock Creek	4		

- Budget : \$900,000
- Sampling Frequency:
 - Regular Sampling: twice on one week and once the following week. Since the sampling was at regular intervals, the data collected represents wet and dry weather conditions.
 - Wet Weather Sampling: 4 – 40 Hr sampling events








SUMMARY OF E.COLI RESULTS






Data Collected in Anacostia River: *E.coli*



Data Collected in Potomac River: *E.coli*



Data Collected in Rock Creek: *E.coli*



Conclusions

- Phase I CSO controls reduced CSO volume by 38% - within the range of accuracy of modeling used to make LTCP predictions.
- DC Water operated Blue Plains conservatively and treated 266 million gallons of combined sewage beyond that required by its NPDES permit in 2015.
- Anacostia River – E.coli
 - Upstream flow entering the District has high concentrations of E.coli and does not typically meet water quality standards. However, the Phase I controls have reduced exceedance frequency of the E.coli water quality standard (geomean of 126 MPN/ 100 ml) by 1-3 months at most of the locations within the District.
 - Noticeable reductions are observed in the bacteria concentrations for the months of May through September.
- Potomac River– E.coli
 - Concentration by which the Potomac River is exceeding the E.coli quality standard (geometric mean of 126 MPN/ 100 ml) is small.
 - CSOs mostly cause transient elevations of bacteria levels in river reaches immediately downstream of outfalls in the Potomac River.
 - Monthly E.coli geomeans is most affected by the boundary conditions and least affected by transient wet weather sources like CSOs and storm water.
- Rock Creek– E.coli
 - Phase I controls did not have any effect in the monthly geometric mean concentrations due to low frequency of CSO discharges to Rock Creek
 - High background concentration of bacteria from upstream sources are evident in the data

Summary of Lessons Learnt – Receiving Water Quality Monitoring

Planning Phase:

- Sampling during winter months may not be feasible due to ice/snow. Plan the sampling program to accommodate some time extension for adequate data collection.
- Uncertainty in weather predictions could result in cancellations. Include adequate contingency in the budget.

Execution Phase:

- Careful planning of timely delivery of samples at the lab is critical. Bacteria has 8 hour maximum holding time.
- Ensure availability of lab, several days in advance before wet weather sampling due to:
 - Very few certified labs are available for bacteria testing in DC Metro. (Used Martel Labs in Baltimore, Maryland for Phase I PCM)
 - Several agencies in the area may be planning to sample for the same rain event. Lab can only accommodate certain number of bacteria samples for analysis at a time.
- Delay in the weather predictions could result in sampling during overnight, weekends and holidays. Notify changes in sampling schedule to the team and the lab as early as practical.
- Ensure availability of logistics - sampling personnel, boats, sampling bottles, labels, adequate bacteria media at lab etc
- Look out for any construction/ dredging work in the project area. Results for certain parameters may be impacted for such an activity.

Future Monitoring

- NPDES Permit Requirements:

Phase	Post-construction Condition
1	Following placement in operation of the inflatable dams and pumping stations rehabilitation
2	Following placement in operation of the Anacostia, Rock Creek and Potomac Storage tunnels, respectively as each tunnel is placed in operation
3	Following placement in operation of the complete CSO Tunnels storage system



An aerial photograph of a large-scale construction project at a water treatment facility. The foreground and middle ground are dominated by several large, circular concrete basins under construction, with some showing wooden formwork. Numerous yellow cranes and construction equipment are scattered across the site. To the right, several completed circular aeration tanks are visible, each with a central mechanical structure. In the background, there are several large, multi-story industrial or office buildings. The facility is situated on a peninsula or near a large body of water, with a city skyline visible in the far distance under a clear blue sky.

Questions

Carlton M. Ray

email: CARLTON.RAY@DCWATER.COM

phone: 202-787-4469